APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Removal of Debris and Berm Cutting in Vemanna Layout, Muneshwara Block, Venkatagiriyappa Layout, A.K Colony, Gopalappa Garden and Doddabommasandra Old Village in ward no 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRADEEPA K A		
				In Figures		In Words
1	807.08	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	78.17	63089.44	Rupees Seventy Eight and Seventeen Paise Only
2	1302.1	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly etc complete as per specifications and directions of engineer in charge of the work	Cum	150.25	195640.53	Rupees One Hundred Fifty and Twenty Five Paise Only
3	2109.18	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading.etc complete as per specifications and directions of engineer in charge of the work	Cum	99.96	210833.63	Rupees Ninety Nine and Ninety Six Paise Only
					469563.60	

Signature of the Contractor

Executive Engineer,
Byarayanapura Division
BBMP, Bangalore - 92

11/3/16

11/03